

LEASE NAME Whelan "OWWO"

WELL NUMBER 2

3300 Ft. from E Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 31 RGE. 11 ~~WEST~~ (W)

COUNTY Barber County, Kansas

Date Well Completed \_\_\_\_\_

Plugging Commenced 08-02-02

Plugging Completed 08-02-02

RECEIVED  
SEP 25 2002  
9-25-02  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Corp. Div.  
office within 30 days.

LEASE OPERATOR CMX, Inc.

ADDRESS 150 N. Main - Suite 1026 Wichita, KS 67202

PHONE#(316) 269-9052 OPERATORS LICENSE NO. 3532

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-31-02 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3835

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each section.

1st Plug: 600' w/50 sacks cement through drillpipe  
2nd Plug: 240' w/50  
3rd Plug: 40' w/10 Rathole w/15 Mousehole w/10

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address PO Box 823 Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CMX, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Douglas H. McGinness II (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well, filed with the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 150 N. Main, Suite 1026 Wichita, KS

DONNA L. MAY-MURRAY  
Notary Public - State of Kansas  
My Appt. Expires 2/7/04

AND SWORN TO before me this 23 day of September, ~~XX~~ 2002

Donna L. May-Murray  
Notary Public

My Commission Expires: 2/7/04

USE ONLY ONE SIDE OF EACH FORM

# Daily Drilling Report

# DRILLING REPORT

Well Name: <b>Whelan #2</b>	API Code: 15-007-20509-0001	Ref Well :
Location W/2 SE NE 29 \ 31S \ 11W	Lease Name: <b>Whelan#2</b>	Ref Loc: -//
County / State: BARBER, KS	Field: Whelan Ext	County: BARBER, KS
GL Level: 1625	Contractor: Duke Drilling Co.	GL Level:
KB Level: 0	Operator: CMX, Inc.	KB Level: 0

Current Date 23-Sep-02

Page 1 of 1

## Daily Drilling Details Report

Date	Start Depth	Daily Remarks
7/31/2002	0	Move in and Rig up today. Will start tomorrow.
8/1/2002	0	Starting to drill on cement. Washed down to 3835'. Circulate for 2 hrs. Make short trip up into the surface pipe. Go back to bottom, circulate 2 hrs and add starch mud. TOH for logs. Rig up Reeves Wireline, ran Dual Induction and Compensated Neutron Density logs. Found that the Synderville interval was to shaley to be productive. Elected not to run repeat formation tester and ordered the well plugged and abandoned. Will send logs when received from Reeves.
8/2/2002		3835' laying down drill pipe to plug. 50 sx @ 600', 50 sx @ 240', 10 sx @ 40', 15 sx in RH, 10 sx in MH, Plugged down @ 8:30 AM.

RECEIVED

SEP 25 2002  
9-25-02  
KCC WICHTTA