

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

15-007-01423-0000

API NUMBER 9/20/58 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Bristol Resources Corporation OPERATORS LICENSE NO. 03048

ADDRESS 6655 South Lewis, Suite 200 Tulsa, OK 74136 PHONE # (918) 492-7900

LEASE (FARM) Ed Sterling WELL NO. 2 WELL LOCATION NENE COUNTY Barber

SEC. 35 TWP. 34S RGE. 13W (E) or (W) TOTAL DEPTH 4915 PLUG BACK TD 4912

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 274' CEMENTED WITH 250 SACKS

CASING SIZE 5-1/2" SET AT 4913 CEMENTED WITH 150 SACKS

PERFORATED AT 4840-84

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug back to 4790 with sand, spot or dump

5 sx cement; cut and recover 5-1/2" casing; bullhead down surface casing with 300# hulls,

10 sx gel, 50 sx cement, 10 sx gel, 100# hulls, casing wiper plug, and 100 sx cement

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not Available IS ACO-1 FILED? N/A
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To Be Determined

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dan Abney PHONE # (918) 492-7900

ADDRESS 6655 South Lewis, Suite 200 Tulsa, OK 74136

PLUGGING CONTRACTOR Clark ^{Corporation} Oilfield Service LICENSE NO. 5105

ADDRESS Medicine Lodge, Kansas PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: D. Abney
(Operator or Agent)

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
SEP 24 1990

September 17, 1990



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

September 24, 1990

Bristol Resources Corp.
6655 South Lewis, Suite 200
Tulsa, OK 74136

Ed Sterling #2
NE NE 35-34-13W
Barber County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801
(316) 225 - 6760