

15-007-30257-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 17 Twp. 33S Rge. (E) 14 (W)
Location as "NE/CNWKSWK" or footage from lines C NE NE
Lease Owner Pickrell Drilling Company
Lease Name McGrath "A" Well No. 1
Office Address 705 4th National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 12, 19 66
Application for plugging filed July 12, 19 66
Application for plugging approved July 12, 19 66
Plugging commenced July 12, 19 66
Plugging completed July 12, 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1029'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 300'. Set plug. Cemented
with 25 sacks cement. Heavy mud to 40'.
Set plug. Cemented with 10 sacks cement
to bottom of cellar. Plugged rat hole with
2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1966
7-27-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebits
705 4th National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 18th day of July, 1966

L. M. Whiting
L. M. Whiting, Notary Public.
My commission expires May 10, 1970



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 6-27-66

Rotary Drilling Completed 7-12-66

LOCATION: McGrath "A" No. 1, C NE NE Section 17-33S-14W,
Barber County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (48 jts.) 8 5/8" surface casing set at 1029', cemented with 500 sacks
cement. Circulated. Completed 6:45 P.M., June 28, 1966. No oil string
run. D. & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

540	Red Rock	C. F. S.
700	Red Bed	3930
1040	Red Rock & Shale	3950
1850	Shale & Shells	4060
1995	Lime & Shale	4740
2030	Lime	
2230	Lime & Shale	
2400	Lime	S. L. M.
3685	Lime & Shale	4520
3825	Shale, Lime & Sand	
3915	Lime & Shale	
4040	Sand & Shale	
4060	Sandy Lime & Shale	
4155	Lime	Slope Test
4218	Lime & Shale	2000
4275	Lime	3000
4366	Lime & Shale	4000
4405	Lime	4500
4518	Lime & Shale	
4545	Lime	
4637	Lime & Shale	
4675	Lime	
4740	Mississippian	

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1966
7-27-66
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss:

On 10th day of July, 19 66, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given Under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting, Notary Public