

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 14 Twp. 33 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 SW 1/4 SE 1/4

Lease Owner Drilling and Exploration Company, Inc.

Lease Name Baier Well No. 1

Office Address 811 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 23 1960

Application for plugging filed September 23 1960

Application for plugging approved September 23 1960


Plugging commenced September 23 1960

Plugging completed September 23 1960

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production None 19    

Was permission obtained from the Conservation Division or its agents before plugging was commenced?     



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation None Depth to top      Bottom      Total Depth of Well 4900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface sand and shale	water	0	150	8 5/8"	314	None
				7"	1236	938

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Filled with mud to 300  
Halliburton plugged with 1/2 sack hulls at 300' with 25 sack plug from  
300' to 230'. Filled with mud to 35'. Pushed Halliburton plug and 1/2  
sack of hulls to 35'. Filled to surface with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 5 1960  
10-3-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mack Oil Co.  
Address Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Karl A. Peterson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl A. Peterson

811 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of September, 19 60

My commission expires September 8, 1963

Eudora Rae Barackman  
Eudora Rae Barackman  
Notary Public.



DRILLING AND EXPLORATION COMPANY, INC.  
Dallas, Texas

DRILLERS WELL LOG

Baier "A" #1 NE SW SE Sec. 14-33S-14W  
Barber County, Kansas  
Commenced R.D.: 8-30-60 Elevation: 1888 K.B.  
Completed R.D.: 9-23-60 Initial Production: Dry  
Total Depth: 4900' Contractor: Mack Oil Company

Casing Record: 307' 8 5/8" O.D. Surface Casing  
1232' 7" O.D. Intermediate Casing

STRATA	DEPTH
Sand	0 - 30
Shale and Redbed	30 - 997
Shale and Shells	997 - 1232
Redbed and Shale	1232 - 1364
Shale and Lime	1364 - 1905
Shale and Shells	1905 - 2050
Lime	2050 - 2697
Lime and Shale	2697 - 3543
Broken Lime	3543 - 3606
Shale	3606 - 3624
Lime	3624 - 3792
Shale and Lime	3792 - 3862
Lime	3862 - 3971
Lime and Shale	3971 - 4093
Lime	4093 - 4188
Sand	4188 - 4249
Lime	4249 - 4900

STATE OF KANSAS  
OCT 3 1960  
10-3-60  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Dallas A. Kirchman

Signed and sworn to in my presence this 30th day of September, 1960, by Dallas Kirchman, representative of Mack Oil Company.

Eudora Rae Barackman  
Eudora Rae Barackman  
Notary Public

My commission expires September 8, 1963