


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County. Sec. 13 Twp. 33S Rge. 14 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
10'E:NE SE SE

Lease Owner Kansas Oil Corporation  
Lease Name Lenker Well No. 1 (TWIN)  
Office Address 400 N. Woodlawn, Suite 20, Wichita, Ks. 67208  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed Feb. 14, 1978  
Application for plugging filed (verbally) Feb. 14, 1978  
Application for plugging approved (verbally) Feb. 14, 1978  
Plugging commenced Feb. 14, 1978  
Plugging completed Feb. 14, 1978  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5194  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

RECEIVED  
FEB 17 1978  
2-17-78  
REGISTRATION DIVISION  
WICHITA, KANSAS

Set 1st plug at 360' with 35 sacks  
2nd plug, 40' solid bridge with 12 sacks  
3 sacks in the rathole.  
Cemented with Halliburton cement.  
Plug was down at 8:00 p.m., February 14, 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February, 1978

Sandra Richman  
Sandra Richman Notary Public.

My commission expires July 21, 1979



CONTRACTOR'S WELL LOG

OPERATOR: Kansas Oil Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Lenker #1A(TWIN)  
 LOCATION: 10' E NE SE SE Section 13-33S-14W  
 Barber County, Kansas  
 SPUD DATE: February 2, 1978  
 COMPLETION DATE: February 14, 1978

0	132	Surface soil & clay
132	367	Red bed
367	1125	Shale & shells
1125	1707	Shale
1707	1793	Lime & shale
1793	2014	Shale & lime
2014	2780	Lime & shale
2780	2960	Shale & lime
2960	3265	Lime & shale
3265	3425	Shale & lime
3425	4675	Lime & shale
4675	5194	Lime
	5194	Rotary Total Depth

Spud hole at 5:20 p.m., February 2, 1978. Drilled 367' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 28# surface casing. Set at 366' K.B. Cemented with 260 sacks of Halliburton Common Cement, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 7:45 a.m., February 3, 1978.

T.D. 5194'. Set 1st plug at 360' with 35 sacks, 2nd plug, 40' solid bridge with 12 sacks, 3 sacks in the rathole. Cemented with Halliburton cement. Plug was down at 8:00 p.m., February 14, 1978. State Plugger - Bill Owens.

RECEIVED  
 REGISTRY DIVISION  
 FEB 17 1978  
 2-17-78  
 WICHITA, KANSAS

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lenker #1A(TWIN), NE SE SE Section 13-33S-14W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge  
 Jack L. Partridge, Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of February, 1978.

Sandra Richman  
 Sandra Richman, Notary Public

My commission expires July 21, 1979.

