


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 13 Twp. 33S Rge. 14 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines

SW SE SE
Lease Owner Kansas Oil Corporation
Lease Name Lenker Well No. 1
Office Address 400 N. Woodlawn, Suite 20, Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry hole
Date Well completed Jan. 31 1978
Application for plugging filed (verbally) Jan. 31 1978
Application for plugging approved (verbally) Jan. 31 1978
Plugging commenced Jan. 31 1978
Plugging completed Jan. 31 1978

Reason for abandonment of well or producing formation _____
Dropped slip in hole
If a producing well is abandoned, date of last production _____
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 930'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug at 150' with 30 sacks
2nd plug at 40' with 30 sacks
30 sacks in rathole
Cemented with 50/50 posmix, 6% gel
Plug was down at 8:00 p.m., January 31, 1978.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Ass't. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 78

My commission expires July 21, 1979
Sandra Richman
Sandra Richman Notary Public.



OPERATOR: Kansas Oil Corporation
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: Lenker #1
LOCATION: SW SE SE Section 13-33S-14W
Barber County, Kansas
SPUD DATE: January 31, 1978
COMPLETION DATE: January 31, 1978

Drilled 367' of 12¼" hole on January 31, 1978. Ratholed ahead 7-7/8" hole to 930'. Coming out of the hole to run surface, dropped slip in hole. Slips dropped to approximately 40'.

Set 1st plug at 150' with 30 sacks, 2nd plug at 40' with 30 sacks, 30 sacks in rathole. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:00 p.m., January 31, 1978. State Plugger - Don Owens.

0 - 930: Clay, shale & sand 930: Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lenker #1, SW SE SE Section 13-33S-14W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

By *Jack L. Partridge*
Jack L. Partridge,
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, on this 3rd day of February, 1978.

My Commission expires July 21, 1979.

Sandra Richman
Sandra Richman, Notary Public

