

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

RECEIVED

JAN 04 2002

NCC WICHITA

WELL PLUGGING RECORD  
K.A.R.-82-3-117

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 15-077-21376-0100  
LEASE NAME Carothers  
WELL NUMBER 1-1H  
2250 ft. from S Section Line  
2250 ft. from E Section Line  
SEC. 1 TWP. 34 RGE. 9 (E) or (W)  
COUNTY Harper  
Date Well Completed  
Plugging Commenced 12/3/01  
Plugging Completed 12/5/01

LEASE OPERATOR McCoy Petroleum Corp.

ADDRESS 453 S. Webb Rd., Suite 310, Box 780208, Wichita, KS

PHONE # (620) 636-2737 OPERATORS LICENSE NO. 5003

Character of well ~~oil~~ Gas per CP 2/3

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 12/3/01 (date)

by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Depth to Top Bottom T.D. 5371

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	268	none
				7	4757	2023

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Bridge plug to 4025, baled 7 sks cem. Load hole, shot pipe at 3412, 3031, 2621, 2422, 2023, came free. Pull to 1450, pump 50 sks cem. Pull to 900, pump 50 sks cem. Pull to 320, circulate with 200 sks cem. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott Hampel (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.


(Signature) Scott Hampel

(Address) 453 S Webb Rd., Ste 310, Box 780208  
Wichita KS 67278

SUBSCRIBED AND SWORN TO before me 3rd day of January 2002

Notary Public

My commission Expires: 9/5/2002




Form CP-4  
Revised 05-88

OK

**Quality Well Service, Inc.****401 West Main****Lyons, KS 67554****RECEIVED****JAN 04 2002****KCC WICHITA****Invoice**

Date	Invoice #
12/12/2001	229

Bill To
McCoy Petroleum Corporation Box 2250 Garden City, KS 67846



		P.O. No.	Terms	Lease Name
			net	Carothers #1-1H
qty	Description	Rate		Amount
34	Rig Time	130.00		4,420.00T
	Trucking	90.00		90.00T
7	Cement	9.00		63.00T
5	Shots	135.00		675.00T
	Torch	35.00		35.00T
	Bored Collar 7"	66.00		66.00T
8	Water Truck	55.00		440.00T
	Out of Town	200.00		200.00T
	Phone Calls	5.00		5.00T
	Clerical Fees	10.00		10.00T
	fresh water	10.00		10.00T
 12/3/01 - 14 hrs. Drove down, found well. rigged up pole, dug cellar and trench. Took head apart. Ran 7" bridge plug to 4025, baled 7 sacks cement on it. Cut surface off to get rest of head off. Had 7" collar welded on. Set floor, loaded hole. Shot pipe at 3412, worked pipe, left on tension. Swedged in and went to room.				
 12/4/01 - 11 hrs. Drove to location, worked pipe, no gain. Shot pipe at 3031, no gain. Worked pipe, shot pipe at 2621, worked pipe, no gain. Loaded backside. Shot pipe at 2422, worked pipe, not loose. Drove in.				
 12/5/01 - 9 hrs. Picked up sand for next well. Drove to location, pumped 110 bls. water, water circulated but pipe didn't come free. Shot pipe at 2023, came free. Pulled to 1450, pumped 50 sacks cement. Pulled to 900', pumped 50 sacks cement. Pulled to 320, circulated with 200 sacks cement. Pulled rest of pipe and tore down. Loaded out.				

**Subtotal** \$6,014.00**Sales Tax (5.9%)** \$354.83**Total** \$6,368.83