


STATE OF KANSAS

STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Harper County, Sec. 1 Twp. 34S Rge. 9 E/W

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C NW $\frac{1}{2}$ SW SW

Lease Owner Robinson Oil Co.

Lease Name Gates

Well No. A-1

Office Address Garvey Building, 300 W. Douglas, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole)

Gas

Date Well completed Oct 22 1973

Application for plugging filed 4-16- 1980

Application for plugging approved 4-16- 1980

Plugging commenced 4-16- 1980

Plugging completed 4-22 1980

Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production

December 15 1979

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens

Producing formation Mississippian Depth to top 4554 Bottom 4567 Total Depth of Well 4567

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	277	None
				4 1/2	4560	3800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CIB set at 4300

Sand from 4300 to 4180

4 sacks cement 4180 to 4140

Ripped at 3880 and 3800 Pulled 3800 feet 4 1/2"

Wood Bridge at 300 Rock to 290

5 yards ready mix

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF KANSAS

COUNTY OF SEDGWICK

Dale M. Robinson

(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

300 W. Douglas, Wichita, KS 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1980

Marilyn A. Slaymaker
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 4-20-81

Marilyn A. Slaymaker
Marilyn A. Slaymaker -- Notary Public.

My commission expires

WELL LOG
Gates A #1
N/2 SW SW 1-34S-9W
Harper County, Kansas

Name of Operator: Robinson Oil Company
R. H. Garvey Bldg.
300 West Douglas
Wichita, Kansas 67202

Date Completed: October 22, 1973

<u>FROM</u>	<u>TO</u>	
0	725	Red Bed and shale
725	1375	Shale
1375	3487	Lime and shale
3487	3540	D. Sand
3540	3778	Lime and shale
3778	3855	S. Sand
3855	4032	Shale and lime
4032	4567	Lime
4567		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Gary L. Hawk
Gary L. Hawk

Subscribed and sworn before me this 24th day of October, 1973.

Mary Ann Schwanborn
Notary Public Barton County

My Commission Expires 7-10-77

