

RECEIVED

SEP 05 2002
9-5-02
Well Plugging Record
K.A.R. -82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

KCC WICHITA

API NUMBER 15-077-20,209-00-01
LEASE NAME Truby A
WELL NUMBER 1-31

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

3165 Ft. from South Line of Section
3190 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION SE SE NW
ADDRESS P. O. Box 780208 Section 31 Township 33 Range 7 W
CITY, STATE, ZIP Wichita, Kansas 67278-0208 County Harper
PHONE # 316-636-2737 Date Well Completed 5/14/01
Character of Well Oil Date Plugging Commenced 7/22/02
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 7/25/02

The plugging proposal was approved on 7/22/02 (date)
by Doug Louis (KCC District Agent's Name)
Is ACO-1 Filed? yes If not, is well log attached?
Producing Formation(s) Miss Depth to Top 4652 Bottom T.D. 4720
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				8-5/8"	268	0
				4-1/2"	4714.5	3407

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sand at 3587', bailed 4 sacks cement. Shot pipe 3529', 3407' worked free. Pull to 1500', pump 35 sacks cement.
Pull to 1000', pump 35 sacks cement. Pull to 320', circulate cement with 150 sacks cement. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc.
Licence No. 31925
Address 401 W. Main City: Lyons State: KS Zip 67554
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick,ss.

Scott Hampel (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) Scott Hampel
(Scott Hampel, Petroleum Engineer)

(Address) 453 S. Webb, Suite 310, P.O. Box 780208 City: Wichita State: KS Zip 67278

SUBSCRIBED AND SWORN TO me this 31 day of August, 20 02



Karen E Houseberg
(Notary Public)

My Commission Expires: 9/5/2002

Form CP-4
Revised 12-92

OR

ALLIED CEMENTING CO., INC.

10516

Federal Tax I.D.# 48-0727860

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Medicine Lodge

Truby A-31

DATE <u>7-25-02</u>	SEC. <u>31</u>	TWP. <u>33 S</u>	RANGE <u>7W</u>	CALLED OUT <u>7:00 AM</u>	ON LOCATION <u>8:00 AM</u>	JOB START <u>9:30 AM</u>	JOB FINISH <u>11:15 AM</u>
LEASE <u>Truby A</u>	WELL # <u>1-31</u>	LOCATION <u>Anthony KS Sw to</u>	COUNTY <u>Harper</u>	STATE <u>KS</u>			
<u>OLD OR NEW</u> (Circle one)		<u>50th AVENUE 1 1/2 S E/S</u>					

CONTRACTOR Quality Well Service OWNER M' Coy Petroleum

TYPE OF JOB OHP

HOLE SIZE _____ T.D. _____ CEMENT AMOUNT ORDERED _____

CASING SIZE 4 1/2 DEPTH 1500' 250 sx 60:40:4% Gel

~~TUBING SIZE~~ 8 3/8 DEPTH 268' used 220 sx

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT Fresh

EQUIPMENT _____

PUMP TRUCK CEMENTER Carl Balding

352 HELPER Dave Felio

BULK TRUCK DRIVER Mark Haas

_____ DRIVER _____

COMMON	<u>132</u>	@	<u>6.65</u>	<u>877.80</u>
POZMIX	<u>88</u>	@	<u>3.55</u>	<u>312.40</u>
GEL	<u>8</u>	@	<u>10.00</u>	<u>80.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>259</u>	@	<u>1.10</u>	<u>284.90</u>
MILEAGE	<u>40</u>			<u>414.40</u>

RECEIVED
SEP 05 2002

TOTAL \$1969.50

REMARKS:

Pump 35 sx - 1500'
35 sx - 1000'
circulate cement to surface
from 320' with 150 sx

KCC WICHITA

DEPTH OF JOB	<u>1500'</u>		
PUMP TRUCK CHARGE			<u>475.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>40</u>	@	<u>3.00</u> <u>120.00</u>
PLUG		@	
		@	
		@	

TOTAL \$595.00

CHARGE TO: M' Coy Petroleum

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX	<u>174.39</u>
TOTAL CHARGE	<u>2738.89</u>
DISCOUNT	<u>256.45</u> IF PAID IN 30 DAYS

SIGNATURE Richard J. McIntyre

PRINTED NAME

Net \$ 2482.44