

15-007-30842-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County: Sec. 20 Twp. 31S Rge. 11 ~~XXX~~ (W)

Location as "NE/CNW/SE" or footage from lines. C NE NE

Lease Owner Bowers Drilling Company, Inc.

Lease Name Watkins Well No. 1

Office Address 1434 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-12 19 65

Application for plugging filed 6-18- 19 65

Application for plugging approved 6-12 19 65


Plugging commenced 6-12 19 65

Plugging completed 6-12 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned; date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	359	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 340'  
Set first plug and bridge at 340'  
with 40 sacks, 1/4 sack hulls  
Filled with heavy mud to 40'  
Set second plug and bridge at 40'  
with 15 sacks cement, 1/4 sack  
hulls, 5 sacks cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1965

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1965

6-22-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Emil E. Bowers (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1965

Hanna J. Miller  
Notary Public.

My commission expires May 1, 1966

WELL LOG

COMPANY: Bowers Drilling Company, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Watkins #1  
 LOCATION: C NE NE Section 20-31S-11W  
 Barber County, Kansas  
 COMMENCED: June 2, 1965  
 COMPLETED: June 12, 1965  
 ELEVATION: 1693 D. F.

0 - 361	Redbed	8-5/8" casing set at 359' with 300
361 - 765	Redbed and shales	sacks cement
765 - 1891	Shale and shells	
1891 - 2035	Lime and shale	
2035 - 2327	Lime	
2327 - 3600	Lime and shale	
3600 - 3750	Shale	
3750 - 3864	Shale & sand - lime	
3864 - 3956	Lime and shale	
3956 - 4315	Lime	
4315 - 4390	Lime and shale	
4390 - 4500	Lime	
4500	T. D.	

## LOG TOPS:

Elgin	3505	Heebner	3671
Douglas	3682	Lansing	3859
Miss. Cong.	4426	Miss. Lime	4465

STATE OF KANSAS            )  
                                   ) SS  
 COUNTY OF SEDGWICK        )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Watkins #1 located C NE NE Section 20-31S-11W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 18th day of June, 1965.

Donna F. Miller, Notary Public

My commission expires May 1, 1966.

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 22 1965  
 6-22-65  
 CONSERVATION DIVISION  
 Wichita, Kansas