

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market  
Wichita, Kansas

WELL PLUGGING RECORD  
K.A.R. 82-3-117

15007-10007-0001  
API NUMBER 5/76

RECEIVED  
JAN 06 2000  
1-6-00  
CONSERVATION DIVISION  
Wichita, Kansas

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

LEASE NAME Watkins  
WELL NUMBER A-1  
4290 Ft. from N/S Section Line  
2310 Ft. from E/W Section Line  
SEC. 20 TWP. 31S RGE. 11 ~~XXXX~~ (W)  
COUNTY Barber  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 12-27-99  
Plugging Completed 12-30-99

LEASE OPERATOR Petroleum Property Services, Inc.  
ADDRESS 155 N. Market, 1010, Wichita, KS 67202-1824  
PHONE# 316 265-3351 OPERATORS LICENSE NO. 31142

Character of Well Casing leak  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-27-99 (date)  
by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? yes  
Producing Formation Douglass Depth to Top 3698 Bottom 3708 T.D. 3835 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	331	None
				4 1/2	3835	2600


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Lay down rods and tubing, set CIBP at 3590, dump 25sx cement with dump bailor, stretch and cut casing at 2600, lay down casing, run 2 3/8 tubing to 600, load hole and spot 50sx, 60/40 6% hek wutg 3% cc, pull tubing to 310 and circulate cement to surface, lay down tubing, top hole off with cement, 60/40 6% on top  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105  
Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Property Services, Inc.

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duty sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Handwritten Signature]  
(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 4 day of January, ~~2000~~ 2000

[Handwritten Signature]  
Notary Public

My Commission Expires: 11/30/04

