


15-007-10007-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
111 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Barber County, Sec. 20 Twp. 31S Rge. (E) 11W(W)  
Location as "NE/CNW/SW" or footage from lines. Cen. SW NW NE  
Lease Owner Lario Oil & Gas Company  
Lease Name Watkins-Speer Unit Well No. 1  
Office Address 301 S. Market, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 13, 1961  
Application for plugging filed (verbal) October 13, 1961  
Application for plugging approved (verbal) October 13, 1961  
Plugging commenced October 13, 1961  
Plugging completed October 13, 1961  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold Hollis  
Producing formation Depth to top Bottom Total Depth of Well 3835' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS					CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	322 Set	@ 331'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Put 20 sacks cement at 325' from bottom, mud to 30'. 10 sacks cement from 30' to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1961  
11-14-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Capitt Drilling, Inc.  
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Leo Ross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
301 S. Market, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of November, 1961

My commission expires July 21, 1962  
[Signature]  
Notary Public.

LARIO OIL & GAS COMPANY  
 Watkins-Speer Unit No. 1  
 Cen. SW NW NE Sec. 20-31S-11W  
 Barber County, Kansas

Drilling Commenced: October 2, 1961  
 Drilling Completed: October 13, 1961  
 Well Completed: October 13, 1961  
 Drilling Contractor: Capitt Drilling, Inc.  
 Total Depth - 3835'  
 I.P. - Dry & Abandoned

CASING RECORD:

8 5/8" 322 (o.a.) Set @ 331'  
 Cem. w/ 250 sacks

<u>Formation</u>	<u>Depth</u>
Surface soil	340
Red bed	505
Shale & shells	1430
Shale & lime	3385
Shale	3445
Lime & shale	3685
Lime	3710
Lime, shale & sand	3835

GEOLOGICAL TOPS - R.B. MEAS.

Elevation	1669 Gr.
	1676 D.F.
	1679 R.B.
Base Le Compton	3464 (-1785)
Elgin Sandstone	3510 (-1831)
Heebner	3622 (-1943)
Douglas Sand Zone	3644 (-1965)
Clean Douglas Sand	3720 (-2041)
Lansing	3815 (-2136)
Rotary T.D.	3835 (-2156)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 14 1961  
 11-14-61  
 CONSERVATION DIVISION  
 Wichita, Kansas