


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber

County. Sec. 20 Twp. 31S Rge. (E) 11 (W)

Location as "NE/CNW&SW&" or footage from lines SW SW SE

Lease Owner. Graham-Messman-Rinehart Oil Company

Lease Name. Dryden "A" Well No. 1

Office Address. 1005 East Second, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 22, 1955 19

Application for plugging filed May 27, 1955 19

Application for plugging approved May 31, 1955 19

Plugging commenced June 11, 1955 19

Plugging completed June 14, 1955 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner, Box 207, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4514 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	212	None
				5 1/2"	4514	2827

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged back with crushed rock
from 4432 to 4400. Dumped 5
sacks cement at 4400' with dump
bailer. Top of cement 4375'.
Filled hole with mud to 210'.
Set rock bridge. Dumped 20
sacks cement. Top of cement 150'.
Filled with mud to 35' and set
rock bridge. Dumped 10 sacks of
cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Joe Jacobs, J&M Casing Pulling Company (License No. 11)

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Gilliland

(employee of owner) or (Notary Public) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.


(Signature)

1005 East Second, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 55

My commission expires November 5, 1958

Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
6-22-55
JUN 22 1955

CONSERVATION DIVISION
Wichita, Kansas

NO. 1 DRYDEN "A"Formerly referred to as - NO. 2 DRYDENWELL RECORDLocation: SW SW SE, 20-31S-11W
Barber County, Kansas

Commenced: February 11, 1955

Operator: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Completed: February 25, 1955

Elevation: 1674 KB

Contractor: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Production:

Casing Record: 8 5/8" @ 212' w/140 sacks cement
5 1/2" @ 4514' w/150 sacks cement

.....L O O.....

Shale-Clay-Gyp	212
Shale	712
Shale-Shells	1625
Line-Shale	1830
Line (Ft. Riley)	1975
Line-Shale	2120
Shale-Line	2250
Line-Shale	2815
Shale-Line	2985
Line-Shale	3670
Douglas Sand	3725
Line-Shale	3860
KO Line	3940
Line-Shale	3970
Line	4431
Chert	4478
Miss.	4514 B.T.D.

Heebner 3643 (-1969)
 Douglas Group 3654 (-1980)
 Douglas Sand 3702 (-2028)
 Brown Line 3841 (-2167)
 Lansing 3851 (-2179)
 Mississippi 4421 (-2747)

RECEIVED
 STATE COMMISSION
 JUN 22 1955
 6-22-55
 CONSERVATION DIVISION
 Kansas

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Hilliland

J. A. Hilliland

Subscribed and sworn to before me this
 7th day of March 1955.

Joseph L. Louis
 Notary Public

My Commission Expires: November 5, 1958

