

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 19 Twp. 31S Rge. 11W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW
Lease Owner E. K. Edmiston
Lease Name McGregor Well No. 1
Office Address 501 First Nat'l. Bk. Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-21-62 19
Application for plugging filed 4-20-62 19
Application for plugging approved 4-20-62 19
Plugging commenced 4-20-62 19
Plugging completed 4-21-62 19

Reason for abandonment of well or producing formation commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4335 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug and 15 sacks cement @ 240'
Plug and 10 sacks cement @ 40'

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1962
4-26-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. K. Edmiston Drilling Co., Inc.
Address 501 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. E. K. Edmiston (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*

501 First Nat'l. Bk. Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 62

My commission expires April 23, 1963

[Signature]
Juanita M. Green Notary Public.



DRILLER'S LOG

COMPANY: E. K. EDMISTON
 501 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

ROTARY DRILLING COMMENCED: APRIL 7, 1962

ROTARY DRILLING COMPLETED: APRIL 21, 1962

WELL NAME: MC GREGOR #1
 SW SW SW SEC. 19-31S-11W
 BARBER COUNTY, KANSAS

CONTRACTOR: E. K. EDMISTON DRILLING CO., INC.
 501 FIRST NATIONAL BANK BUILDING
 WICHITA 2, KANSAS

CASING RECORD: 8 5/8" @ 250' w/ 225 sacks

LOG


Measurements from top of Rotary Bushing:

0 - 90	Sand
90 - 185	Shale and Shells
185 - 250	Shale and Shells
250 - 655	Shale
655 - 1090	Shale
1090 - 3232	Lime and Shale
3232 - 3375	Shale and Lime
3375 - 3387	Shale and Sand
3387 - 3500	Shale, Lime and Sand
3500 - 3585	Shale and Sand
3585 - 3715	Shale and Lime
3715 - 3785	Lime and Shale
3785 - 4275	Lime
4275 - 4335	Lime and Chert
<u>4335</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATIONS COMMISSION
 APR 23 1962
 4-26-62
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, E. K. Edmiston, President of the E. K. Edmiston Drilling Company, Inc., hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

E. K. Edmiston Drilling Co., Inc.



 By _____
 E. K. Edmiston, President

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 24th day of April, 1962, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument as President and in behalf of the E. K. Edmiston Drilling Company, Inc. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:
April 23, 1963



 Juanita M. Green, Notary Public