

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-10334

LEASE NAME Lasswell

WELL NUMBER 2

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 20 TWP. 33S RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed 11/01/43

Plugging Commenced 9/11/90

Plugging Completed 9/13/90

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chevron U. S. A. Inc.

ADDRESS P. O. Box 36366, Houston, TX 77236

PHONE# ( 713 ) 561-3602 OPERATORS LICENSE NO. 4519

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/13/90 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Chat Depth to Top 4815 Bottom 4862 T.D. 5072

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi Chat	gas	4815	4862	10-3/4"	296'	none
				7"	5041'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Set CICR @ 4775', load hole w/9# mud, pump 20 sks Cl 'A' thru CICR and 5 sks on top, perf @ 620' w/4 SPF. Pump 180 sks Class 'A' B-J Lite @ 12.4#/gal, circ to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A

Address P. O. Box 963, Pratt, KS 67124 (316-672-5593)

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chevron U.S.A. Inc., Attn: Sharon L. Houk

STATE OF Texas COUNTY OF Harris, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon L. Houk

(Address) P.O. Box 36366, Houston, TX 77236

SUBSCRIBED AND SWORN TO before me this 24 day of Oct., 19 90

[Signature]  
Notary Public

My Commission Expires: 2-15-93

