

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Barber County. Sec. 30 Twp. 33S Rge. 13 (E) W (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW SE SW

Lease Owner J. M. Huber Corporation

Lease Name Rambo Well No. 1

Office Address 916 South Pine St. - Box 8 - Pratt, Kans

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed June 24, 1948 19.

Application for plugging filed June 24, 1948 19.

Application for plugging approved June 24, 1948 19.

Plugging commenced June 24, 1948 19.

Plugging completed June 25, 1948 19.

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. E. Stough

Producing formation Depth to top Bottom Total Depth of Well 5325' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Top of Arbuckle 5310', 10 3/4" 29# Spiral Weld, 360', 300 Sacks Cement, None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted first Plug at 250' in Pipe and put in 20 sacks of cement on top of plug. Filled hole with mud on up to within 30' of surface and put in 15 sacks of cement in top which came to the base of the Cellar.

Handwritten date stamp: JUN 25 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corporation Box 8 Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 8 - Pratt, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25th day of June 19 48

My commission expires

Handwritten signature of Notary Public

PLUGGING FILE SEC 30 T 33 R 13 BOOK PAGE 40 LINE 18

DRILLER'S LOG

COMPANY: J. M. HUBER CORPORATION
 CONTRACTOR: J. M. HUBER CORPORATION
 FARM NAME: NO. 1 RAMBO

LOCATION: NW SE SW 30-33S-13W
 Barber County, Kansas

COMMENCED: 5-26-48
 COMPLETED: 6-25-48

ELEVATION: 1833
 PRODUCTION: DRY & ABANDONED

CASING USED: 10" at 300'

Cellar	5
Sand	20
Red Bed & Shells	850
Shale & Shells	1700
Anhydrous shells & shale	1870
Brown Lime & Shale	2055
Shale & Lime Shells	2070
Lime & Shale Breaks	2135
Lime & Rough Shale	2215
Lime & Shale	2310
Lime	2330
Shale & Shells	2485
Shale & Lime	2550
Lime & Shale	2630
Lime	2690
Lime & Shale	2895
Lime & Shale Streaks	2980
Lime & Shale	3250
Shale & Lime	3330
Lime & Shale	3390
Brown Lime & Shale	3605
Lime & Shale	3695
Shale	3760
Lime & Shale	3810
Shale & Shells	3865
Shale & Lime	3910
Lime & Shale	3938
Shale & Shells	3958
Shale	4000
Shale & Lime Shells	4040
Shale & Shells	4060
Lime	4140
Shale & Shells	4200
Lime & Shale Streaks	4240
Lime & Shale	4283
Lime	4349
Lime & Sand Streaks	4376
Sand	4394
Lime & Sand Streaks	4406
Lime	4584
Shale & Lime	4624
Lime & Shale	4650
Lime	4689
Lime & Shale	4732
Lime Chert & Shale	4760
Lime	4784
Cherty Lime & Shale	4826
Cherty Lime & Shale Streaks	4840
Lime	4880
Lime & Shale Streaks	4905
Shale & Lime Streaks	4950
Lime & Shale	5018
Shale	5087
Lime	5110
Lime & Shale	5128
Lime	5149
Lime (Hard & Cherty)	5169
Lime cherty	5185
Lime	5204
Sand	5211
Sand & Shale	5244
Shale	5311
Arbuckle Lime	5325
Total Depth	5325

SAMPLE TOPS:

Top Lansing 4210
 Mississippi Lime 4741
 DST 4754-84, open 30 minutes, (fair blow-no gas to surface) recovered 30' mud, no show
 DST 4788-4840, open 30 minutes, recovered 30' mud, no shows.
 DST 4840-80, open 30 minutes, recovered 30' mud, no shows.
 Top Viola 5089
 Simpson 5204
 Top Arbuckle 5310-25, Rotary Total Depth. DRY & ABANDONED.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log of the Rambo No. 1, located in the Northwest Quarter of the Southeast Quarter of the Southwest Quarter (NW SE SW), of Section Thirty (30), Township Thirty-three (33) South, Range Thirteen (13) West, Barber County, Kansas.

E. A. Huffman
 E. A. Huffman, District Manager
 J. M. HUBER CORPORATION

Subscribed and sworn to before me this 13th day of August, 1948.

Annetha J. Farrell
 Notary Public

My commission expires June 7, 1950.

