

15-007-01660-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 30 Twp. 33 Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines C SW SW

Lease Owner Osage Oil & Gas Co., Inc.

Lease Name Hendrix Well No. 1

Office Address 709 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 8 1957

Application for plugging filed January 8 1957

Application for plugging approved January 8 1957


Plugging commenced January 8 1957

Plugging completed January 8 1957

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	316'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (4900') to 300'. Set plug #1 and 20 sacks cement to 225'. Filled hole with extra heavy rotary mud to 35'. Set plug #2 and 10 sacks cement to 3'.

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol

814-16 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 57

Darlene May
Notary Public.

My commission expires September 30, 1959

PLUGGING
FILE SEC 30 T 33 R 13 W
BOOK PAGE 132 LINE 43

ROTARY DRILLING LOG

OPERATOR: Osage Oil and Gas Co., Inc.
Hendrix No. 1
C SW SW Sec. 30-33-13W,
Barber County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 12/23/56
COMP: 1/8/57

Formations:

Shale & Shells	228'
Shale & Red Rock	316'
Red Bed & Shale	1140'
Shale & Red Rock	1680'
Shale & Shells	1940'
Lime & Shale	2198'
Lime & Shale Streaks	2317'
Lime & Shale	2430'
Lime	2520'
Shale & Lime Streaks	2618'
Lime & Shale	2760'
Lime	2805'
Shale & Lime	3548'
Sand & Sandy Shale	3615'
Lime	3750'
Shale & Lime	3985'
Lime	4055'
Sandy Shale	4090'
Shale & Lime	4195'
Lime	4890'
Shale	4900'

Rotary Total Depth (D&A) 4900'


Remarks: Set 8-5/8" surface casing
at 316' cemented with 300 sacks
regular cement, 2% C.C.

We certify the above log is true
and correct to the best of our
knowledge and belief.

CAPITT DRILLING, INC.

R.R. McNicol

R. R. McNicol



STATE CORP. REG. DIVISION
1-12-57
CONSERVATION DIVISION
Wichita, Kansas