


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barber County, Sec. 10 Twp. 30 Rge. 12 (E) W (W)

Location as "NE/CNW&SW¼" or footage from lines NE SW SW
Lease Owner Carmerson K. Reed
Lease Name House B#1 Well No. _____
Office Address Kansas City, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/6/69 _____ 19____
Plugging completed 6/10/69 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4532 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	372	none
				4 1/2"	4630'	3416'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, dumped 4 sacks of cement on bottom at 4313',
rigged up on 4 1/2", had 18" tension. Shot pipe at 3522', 3427',
worked pipe. Spotted 60 barrels oil, chased plug to 3400' and
worked pipe. Made 8" tension, pulled 105 joints of 4 1/2" casing.
Bailed hole to 250', set 10' rock bridge and dumped 25 sacks of
cement. Mudded to 40', 10' rock bridge and dumped 10 sacks of
cement. Talled pipe.

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of June, 19 69

My commission expires 2/15/71

Margaret Bruchner
Notary Public.

DRILLERS LOG

#1 House "B"

CASING RECORD:
372' of new 8-5/8"
surface casing

COMPANY: Cameron K. Reed
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NE SW SW
Section 10-308-12W
Barber County, Kansas

TOTAL DEPTH:
4632'

COMMENCED: July 25, 1967
COMPLETED: August 5, 1967

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	44	Ran 372' of new 8-5/8" surface casing; set and cemented at 372' with 220 sacks of common cement and 2% gel. Plug down at 6:00 A. M. July 26, 1967.
Sand & Shale	44	510	
Shale & Shells	510	1870	
Lime & Shale	1870	3290	
Lime	3290	3390	
Shale & Lime	3390	3812	
Lime	3812	4632	

Total Depth 4632'

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1969
CONSERVATION DIVISION
Wichita, Kansas

Ran 143 joints (4632') of 4 1/2' casing; set and cemented at 4630' with 200 sacks of 60-40 posmix, salt saturated. Plug down at 8:30 P. M. August 5, 1967.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 7th day of August, 1967.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

