

2 100498

4-28

API NUMBER 15- 077-21,190-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NE, SEC. 13, T 32 S, R 6 W/EX

3630 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3964

Lease Name Drouhard Well # 32-13

Operator: Macey & Mershon Oil, Inc.

County Harper 156.81

Name & Address 1600 Broadway, #2150

Well Total Depth 4825' feet

Denver, CO 80202-4970

Conductor Pipe: Size \_\_\_\_\_ feet

303-861-9183

Surface Casing: Size 8-5/8 feet 212'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co. Inc. License Number 5929

Address Great Bend, KS

Company to plug at: Hour: 1:00p Day: 28 Month: 4 Year: 1989

Plugging proposal received from Sally Byers

(company name) Duke Drilling Co., Inc. (phone) \_\_\_\_\_

were: 35 @ 1000' - 35 @ 600' - 35 @ 260' - 25 @ 60' - 10 @ R.H.

Plugging Proposal Received by Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:30p Day: 28 Month: 4 Year: 1989

ACTUAL PLUGGING REPORT Fill hole w/mud to 1000' - spotted 35 sx cement below salt - pulled pipe to 600' & spotted 35 sx cement above salt - pulled pipe to 260' & spotted 35 sx below surface - put 25 sx at 60' to surface & 10 sx in rat hole.

RECEIVED STATE CORPORATION COMMISSION

MAY 8 1989

Allied #977 60/40 4% gel

Remarks: \_\_\_\_\_ CONSERVATION DIVISION (if additional description is necessary, use BACK of this form.)

INVOICED

I (XXXXXX did not) observe this plugging.

DATE 5-10-89

INV. NO. 24707

Signed J.L. Sanders (TECHNICIAN)