

2 040326

-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,383-A

SW NW NW, SEC. 10, T 32 S, R 6 W/8

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Hostetler Well # B-1

Operator: Texas Energies

County Harper 149,89

Name & Address P.O. Box 947

Well Total Depth 4612 PB 4355 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Mark

(company name) Kelso Casing Pulling (phone) _____

were: Sand back to 4250' and four sacks. Then 3 hulls, 15 gel and 100 sacks cement.

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 Day: 28 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2" casing to 4250' to cover the:

perfs. The sand was capped with four sacks cement. The casing was shot off
and recovered. The top was squeezed plugged by pumping 3 sacks of hulls, 15 sacks
of gel and 100 sacks of 60/40 poz cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 - 1987 5-6-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-87

INV. NO. 16838

WC

Signed [Signature]
(TECHNICIAN)