

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-02492-00-00
Spot: SESESENW Sec/Twnshp/Rge: 3-22S-19E
2700 feet from S Section Line, 2740 feet from E Section Line
Lease Name: SETTLE Well #: 1
County: ANDERSON Total Vertical Depth: 842 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
SURF	10	0		0 SX

Well Type: OIL UIC Docket No: B08434.0 Date/Time to Plug: 10/16/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF CEMENT. RUN WORKSTRING DOWN BACKSIDE OF 2" TO TOP OF OLD CEMENT, AND PUMP CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP BACKSIDE UP WITH CEMENT. TIE ONTO 2" AND SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF PRESSURE WAS ACHIEVED. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE
Date/Time Plugging Completed: 10/17/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

PULLED OUT 825FT OF 2". RAN WORKSTRING 825' INSIDE 5" AND RAN A WORKSTRING ON OUTSIDE OF 5" DOWN TO 700'. PUMPED CEMENT TO SURFACE THROUGH BOTH WORKSTRINGS. PULLED WORKSTRINGS OUT AND TOPPED WELL OFF WITH CEMENT. NEXT DAY TOPPED WELL OFF WITH CEMENT BEFORE MOVING TO NEXT LOCATION. 290 SACKS USED TO PLUG WELL.


Perfs:

Remarks:

Plugged through: TBG

District: 03

Signed

 (TECHNICIAN)

RECEIVED

JAN 08 2014

KCC Chanute Dist. #3

FS