

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23988-00-00
Spot: SENENW Sec/Twnshp/Rge: 13-8S-22W
1155 feet from N Section Line, 2310 feet from W Section Line
Lease Name: KRAUS Well #: 1
County: GRAHAM Total Vertical Depth: 3718 feet

Operator License No.: 34975
Op Name: STRATAKAN EXPLORATION, LLC
Address: 204 W. MILL ST.
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/15/2013 12:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: TERRY Company: WHITE KNIGHT DRILLING LLC Phone: (785) 303-8005

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 12/15/2013 10:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1650 w/25 sx
2nd plug @800 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: GLOBAL
Plugged through: DP

District: 04

Signed CASE MORRIS
01/22/14 (TECHNICIAN)

DEC 16 2013

KCC WICHITA
DEC 19 2013
RECEIVED