

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22718-00-00
Spot: E2SWNWNW Sec/Twnshp/Rge: 6-13S-15W
4290 feet from S Section Line, 4660 feet from E Section Line
Lease Name: BRUNGARDT "D" Well #: 3
County: RUSSELL Total Vertical Depth: 3368 feet

Operator License No.: 33996
Op Name: V. FRANCIS WEIGEL FAMILY PARTNE
Address: PO BOX 219
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3368		215 SX
SURF	8.625	924		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2013 1:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY W. PIESKER Company: WEIGEL FAMILY PARTNERSHIP Phone: (785) 735-4363

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement and 800 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2013 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforations: 350' and 914'.
Casing holes at 1880'. Worked on it 4 days with mills and shoes to get through. Only made 8' and got hung up and had trouble getting tubing back out.
Ran tubing to 1860' and pumped 200 sx cement w/600 # hulls mixed in the last 125 sx cement. Pulled tubing to 1000' and pumped 120 sx cement w/200 # hulls. Cement circulated out backside at 115 sx cement. POOH. Hooked to casing and pumped 15 sx at 350 psi and shut in. Dug out braden head and found to be full of cement.

GPS: 38.95544 -099.03708

KCC WICHITA
JAN 02 2014
RECEIVED

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Ray A Dinkel
01/22/14 (TECHNICIAN) CM

DEC 26 2013