

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20811-00-01
Spot: SESESE Sec/Twnshp/Rge: 17-11S-31W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: ENGEL Well #: 2
County: GOVE Total Vertical Depth: 4565 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4070		
PROD	4.5	4658		230 SX
SURF	8.625	291		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2013 12:00 PM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: PETE FIORINI Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
8 5/8" surface casing set at 291' w/200 sx cement. 4 1/2" production casing set at 4658' w/230 sx cement. TD 4565', PBTD 4490', DV tool set at 2498'. Cement did not circulate. TOC at 1490'. 4 1/2" casing perforated at 1460'. Cement to surface with 400 sx cement. Perforations: 4556' - 4559'. Squeezed with 50 sx (Johnson), 4550' - 4551', 4478' - 4482', 4458' - 4460, 4326' - 4331', 4215' - 4219', 4049' - 4052', 4014' - 4016', 3999' - 4001'. CIBP's set at 4030' and 4070 left in well. Casing leak at 3520'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2013 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4000' and pumped 90 sx cement w/250 # hulls. Pulled tubing to 2702' and pumped 90 sx cement w/300 # hulls. Pulled tubing to 1355' and pumped 95 sx cement w/200 # hulls. Circulated cement to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Casing full of cement. Connected to 8 5/8" surface casing and pumped 10 sx cement.

GPS: 39.09160 N -100.77730 W

Perfs:

Top	Bot	Thru	Comments
4556	4560		
4550	4552		
4478	4482		
4458	4460		
4326	4331		
4215	4218		
4049	4052		
4014	4014		
3996	4001		

KCC WICHITA
JAN 02 2014
RECEIVED

Remarks: ULTIMATE WELL SERVICE AND CONSOLIDATED CEMENT COMPANY TICKET # 38,116

Plugged through: TBG

District: 04

Signed Darrel Dipman
10/21/14 (TECHNICIAN)

CM

Form CP-2/3

DEC 30 2013