

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22693-00-01

Spot: SEWNNE

Sec/Twnshp/Rge: 14-6S-23W

990 feet from N Section Line, 1650 feet from E Section Line

Lease Name: KEMPER 14A

Well #: 2

County: GRAHAM

Total Vertical Depth: 3815 feet

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3813		125 SX
SURF	8.625	246		165 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/27/2013 9:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOMMY ATKINS

Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
PC @ 2024' w/400 sx cement. Lost circulation. Ran log. Cemented top at 692'. Pumped 125 sx cement down backside until full. Tubing stuck in hole at 3610'. Can't get any more tubing out.
Perforations: 3751' - 3754'

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/27/2013 12:45 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2800' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out of hole. Tied on to casing and squeezed w/20 sx cement. Shut in w/400 psi. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 150 psi.

GPS: 39.53623 -099.85049

Perfs:

Top	Bot	Thru	Comments
3751	3754		
3649	3652		
3605	3608		

Remarks: ALLIED CEMENTING TICKET # 61112

KCC WICHITA

JAN 06 2014

Plugged through: TBG

RECEIVED

District: 04

Signed

[Signature]
01/20/14
(TECHNICIAN)

CM

DEC 30 2013