

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23455-00-00
Spot: NWNESWSW Sec/Twnshp/Rge: 29-30S-11W
1143 feet from S Section Line, 690 feet from W Section Line
Lease Name: THOM RANCH Well #: 1-29
County: BARBER Total Vertical Depth: 4892 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3725		WITH 2 SX CMT
CIBP		4250		
CIBP		4750		
PROD	4.5	4660	2312	WITH 200 SX CMT
SURF	10.75	220		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/19/2013 10:30 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316) 215-1683

Proposed Plugging Method: SET CIBP @ 3725' & 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 75 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2013 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3725' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 725' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 267' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4272	4273		
3772	3784		
3762	3770		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

RECEIVED

DEC 31 2013

KCC DODGE CITY

Signed

Stephen J Pfeifer
on 12/19/13

(TECHNICIAN)