

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21716-00-00
Spot: W2SESENE Sec/Twnshp/Rge: 9-34S-17W
2310 feet from N Section Line, 510 feet from E Section Line
Lease Name: CJR 3417 Well #: 1-9
County: COMANCHE Total Vertical Depth: 5685 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4925		WITH 5 SX CMT
CIBP		5040		
PROD	5.5	5685	1200	WITH 850 SX CMT
SURF	8.625	665		WITH 360 SX CMT

Well Type: SIOW UIC Docket No: _____ Date/Time to Plug: 12/18/2013 8:00 AM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE Phone: (405) 429-5500

Proposed Plugging Method: SET CIBP @ 4925' WITH 5 SX CMT. PLUG AT 960' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: NONE
Date/Time Plugging Completed: 12/18/2013 5:45 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

SET CIBP @ 4925' WITH 5 SX CMT. 1ST PLUG AT 945' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 684' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5064	5398		
5061	5064		
5000	5006		
4974	5006		

KCC WICHITA

DEC 31 2013

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

DEC 19 2013

KCC DODGE CITY

Signed

Daniel Sellers
01/20/14 (TECHNICIAN)