

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21706-00-00
Spot: S2N2NWNE Sec/Twnshp/Rge: 21-34S-19W
350 feet from N Section Line, 1980 feet from E Section Line
Lease Name: EASTON 3419 Well #: 1-21
County: COMANCHE Total Vertical Depth: 6140 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5280		WITH 2 SX CMT
CIBP		5365		
CIBP		5630		
CIBP		5961		
COND	20	110		WITH 6 SX CMT
PROD	5.5	6132	3200	WITH 1225 SX CMT
SURF	8.625	834		WITH 435 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2013 8:00 AM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Revd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: CIBP @ 5280' WITH 2 SX CMT. PLUG AT 860' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 12/16/2013 3:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 5280' WITH 2 SX CMT. 1ST PLUG AT 849' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 62' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5987	5996		
5650	5683		
5512	5599		
5377	5490		
5330	5341	CSG	

KCC WICHITA
DEC 20 2013

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

RECEIVED

Plugged through: TBG

District: 01

RECEIVED

DEC 19 2013

KCC DODGE CITY

Signed

(TECHNICIAN)