

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20245-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 19-17S-35W
400 feet from N Section Line, 400 feet from E Section Line
Lease Name: MAZANEC 1735 Well #: 1-19
County: WICHITA Total Vertical Depth: 5100 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	1550		WITH 775 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/19/2013 5:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVID MEZA Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5500

Proposed Plugging Method: 1ST PLUG AT 2370' WITH 50 SX CMT. 2ND PLUG AT 1580' WITH 70 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: NONE
Date/Time Plugging Completed: 12/19/2013 7:00 AM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2370' WITH 50 SX CMT. 2ND PLUG AT 1580' WITH 70 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

KCC WICHITA
DEC 31 2013
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Daniel Sellers
01/24/14 (TECHNICIAN)

RECEIVED
DEC 19 2013
KCC DODGE CITY