

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21705-00-00

Spot: SWNENWNE

Sec/Twnshp/Rge: 35-33S-19W

335 feet from N Section Line, 1820 feet from E Section Line

Lease Name: RANDELL 3319

Well #: 1-35

County: COMANCHE

Total Vertical Depth: 6120 feet

Operator License No.: 34192

Op Name: SANDRIDGE EXPLORATION AND PRO

Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5150		WITH 2 SX CMT
CIBP		5414		
PROD	5.5	6120	3225	WITH 300 SX CMT
SURF	8.625	924		WITH 580 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/18/2013 8:00 AM

Plug Co. License No.: 34982

Plug Co. Name: TITAN WELL SERVICE, LLC

Proposal Rcvd. from: ANTHONY

Company: TITAN WELL SERVICE, LLC

Phone: (405) 828-4225

Proposed
Plugging
Method:

SET CIBP @ 5150' & 2 SX CMT. PLUG AT 960' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 12/18/2013 4:30 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 5150' WITH 2 SX CMT. 1ST PLUG AT 954' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5493	5497		
5476	5484		
5436	5448		
5200	5292		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

DEC 20 2013

RECEIVED

District: 01

RECEIVED

DEC 19 2013

KCC DODGE CITY

Signed

Richard W. Lacey
01/20/14

(TECHNICIAN)