

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01902-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 25-18S-8W  
4932 feet from S Section Line, 1663 feet from E Section Line  
Lease Name: AINSWORTH SAM Well #: 9  
County: RICE Total Vertical Depth: 3203 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	6	3000		
PROD	6	3153	140	SX
SURF	10.75	201	250	SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2013 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (785) 483-4096

Proposed Plugging Method: AS PER KCC RULES & REGS. WELL HAD BEEN DENIED TA DUE TO HFLD.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/20/2013 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, TAG BOTTOM @ 2960'. PERFORATE AT 1050', 700' AND 250'. RUN TUBING TO 2960' AND PUMP DRILLING MUD FOLLOWED BY 50 SX'S CEMENT. PULLED TUBING TO 1050', AND PUMP 100 SX'S CEMENT WITH 3% CC. LET SET FOR AWHILE, TAGGED CEMENT @ 800'. RUN TUBING TO 750' AND PUMPED 75 SX'S CEMENT - CIRCULATED CEMENT AND MUD OUT OF HOLE. PULL TUBING OUT AND TOPPED OFF WITH 5 SX'S CEMENT. CONNECTED ONTO SURFACE CASING AND PUMPED 40 SX'S CEMENT -- PRESSURED UP TO 300#S -- HELD PRESSURE.

KCC WICHITA  
JAN 02 2014  
RECEIVED

Remarks: COPELAND TICKET #40582. LOG TECH OF KS #7760. - DENIED TA

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*  
01/20/14  
(TECHNICIAN)