

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR MULL DRILLING COMPANY, INC.

API NO. 15-077-20,737-00-00

ADDRESS P.O. Box 2758
Wichita, KS 67202

COUNTY Harper County, Kansas

FIELD Spivey-Grabs

**CONTACT PERSON Patricia L. Ungleich
PHONE 264-6366 or 264-5368

PROD. FORMATION Mississippian

LEASE DRAKE

PURCHASER Permian Corporation

WELL NO. #2

ADDRESS 9810 E. 42nd
Tulsa, OK 74145

WELL LOCATION 133' S of NE NE

520' Ft. from North Line and

660' Ft. from East Line of

the NE/SEC. 14 TWP. 31S RGE. 9W

DRILLING Landmark Energy Corporation


CONTRACTOR P.O. Box 18595

ADDRESS Wichita, KS 67218

PLUGGING NA

CONTRACTOR

ADDRESS



WELL PLAT

KCC
KGS
MISC
(Office Use)

TOTAL DEPTH 4422 PBD NA

SPUD DATE 11/11/81 DATE COMPLETED 11/22/81

ELEV: GR 1650 DF 1653 KB 1655

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	24#	250'	Commn	225 sx	2% gel, 3% cc
Production	7-7/8"	4-1/2"	10 1/2#	4397'	Scavenger	25 sx	
				Open Hole	50-50 Poz	150 sx	2% gel, 10% salt

RECEIVED
STATE CORPORATION COMMISSION RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
<u>APR - 7 1982</u>					

CONSERVATION DIVISION RECORD

Size	Wichita, Kansas depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Ac 500 gal MA 12/7/81	4397'
Frac w/ 5000# 20-40 sand 12/9/81	4397'

Date of first production 1/3/82 Producing method (flowing, pumping, gas lift, etc.) Pumping Gravity 28.5%

RATE OF PRODUCTION PER 24 HOURS Oil 28 BOPD Gas 3 BOPD Water % 2 BOPD Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Sold Perforations NA

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unknown Depth NA
 Estimated height of cement behind Surface Pipe Circulated
 DV USED? NA

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
See Drillers Log Attached				
	3479	-1844	Heebner	
	3545	-1890	Douglas	
	3664	-2009	Lansing	
	4091	-2436	Stark Sh	
	4191	-2536	B/KC	
	4324	-2669	Cherokee	
	4393	-2738	Mississippian	
	4427	-2772	LTD	
DST #1 4354-4422/30-45-60-60 (Miss)				
Gas to surface in 1 min.				
First Flow:				
Gauge: 5 min.	764	MCFG		
10 min.	456	MCFG		
20 min.	319	MCFG		
30 min.	283	MCFG		
Second Flow:				
Gauge: 2 min.	499	MCFG		
20 min.	353	MCFG		
30 min.	195	MCFG		
40 min.	169	MCFG		
50-60	169	MCFG (stabilized)		
Recovered:				
60' oil & gas cut mud				
120' clean gassy oil				
780' froggy gassy oil				
ISIP 966 IFP 243-285 FFP 264-285 FSIP 924				

A F F I D A V I T

STATE OF KANSAS, COUNTY OF Harper SS,

Robert O. Wall OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,
 DEPOSES THAT HE IS President (FOR)(OF) MULL DRILLING COMPANY, INC.


OPERATOR OF THE Drake LEASE, AND IS DULY AUTHORIZED TO MAKE
 THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 22nd DAY OF November, 19 81, AND THAT
 ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Robert O. Wall
 Robert O. Wall, President

SUBSCRIBED AND SWORN BEFORE ME THIS 30th DAY OF March 19 82



Patricia L. Ungleich
 NOTARY PUBLIC
 Patricia L. Ungleich

MY COMMISSION EXPIRES: March 27, 1983