

12-22

2-040752

73
P

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 07 1993

CONSERVATION DIVISION
WICHITA, KS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,769-00-00

C SW NE, SECTION 11 TOWNSHIP 34 RANGE 9W

OPERATOR LICENSE # 4677 3300 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR Cara Ventures
NAME & P. O. Box 287
ADDRESS Attica, KS 67009

LEASE NAME: Martin "D" #1
COUNTY: Harper
WELL TOTAL DEPTH: 4579' 148.82

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 260'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Paul Caragianis
COMPANY NAME: Cara Ventures PHONE: _____
WERE: 5-1/2" @ 4574' - OH 4574-79' - CIBP @ 4524' & 2 sx -
35 sx @ 1350' - 35 sx @ 900' - circ 310'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

COMPLETED: HOUR: 0945 DAY: 22 MONTH: 12 YEAR: 1992

ACTUAL PLUGGING REPORT:
CIBP set @ 4524' & capped w/2 sx cmt - 5-1/2" csq
shot loose from 2611' & pulled to 1334' & 35 sx cmt
spotted - 5-1/2" pulled to 904' & 35 sx cmt spotted -
5-1/2" pulled to 314' & cmt circ to surf - remaining 5-
1/2" pulled from wellbore and cmt topped off.

REMARKS: Allied #2727 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 1-12-93

WV. NO. 37183
12-22-92

151

Steve Van Gieson (AGENT)