

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20452-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 17-28S-30W
889 feet from N Section Line, 1716 feet from W Section Line
Lease Name: SHADOW Well #: 3-17
County: GRAY Total Vertical Depth: 5300 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1750		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/22/2013 12:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Revd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: PARTIAL
Date/Time Plugging Completed: 12/12/2013 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. DRILLED OUT 60' PLUG & RAN CBL DUE TO BASKET @ EITHER 120' OT 210'. CMT BOND LOG WAS GOOD FROM 820' TO 0'. FILLED 8 5/8" WITH REDIMIX FROM 100' - 0'. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL & REDIMIX BY ALLIED.

Plugged through: DP

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

Signed

[Signature]
11/18/14

(TECHNICIAN)

RECEIVED

DEC 19 2013

KCC DODGE CITY

[Handwritten mark]