

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00404-00-00  
Spot: NWSE Sec/Twnshp/Rge: 10-34S-41W  
1959 feet from S Section Line, 1937 feet from E Section Line  
Lease Name: BAUGHMAN Well #: 1-10  
County: MORTON Total Vertical Depth: 2328 feet

Operator License No.: 33136  
Op Name: ANADARKO E & P ONSHORE LLC  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2120		WITH 15 SX CMT
PROD	4.5	2328	0	WITH 700 SX CMT
SURF	7	573		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2013 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: MIGUEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2120' WITH 15 SX CMT. PLUG AT 1550' WITH 25 SX CMT. PERFORATE @ 150'. PUMP CMT FROM 673' TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2120' WITH 15 SX CMT. 1ST PLUG AT 1550' WITH 25 SX CMT. RAN COLLAR SPLIT SHOT @ 501' & 303'. COULD NOT PULL CASING. RAN CBL. TOC @ 160'. PERFORATE AT 150'. RAN TBG TO 678' & CIRCULATE CMT TO SURFACE UP 4 1/2" CASING AND FROM 150' TO 0' IN THE 4 1/2" X 8 5/8" ANNULUS USING A TOTAL OF 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2170	2273		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

RECEIVED

DEC 19 2013

KCC DODGE CITY

Signed

(TECHNICIAN)