

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20529-00-00
Spot: NENESESW Sec/Twnshp/Rge: 29-32S-36W
1242 feet from S Section Line, 2549 feet from W Section Line
Lease Name: KUHN Well #: 2-29
County: STEVENS Total Vertical Depth: 3150 feet

Operator License No.: 33136
Op Name: ANADARKO E & P ONSHORE LLC
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		668		
CIBP		2900		WITH 5 SX CMT
CIBP		3150		
PROD	4.5	3149	0	WITH 300 SX CMT
SURF	8.625	653		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/23/2013 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2900' WITH 2 SX CMT. LOAD HOLE WITH MUD. SPOT 20 SX CMT AT 1750'. PERFORATE AT 700' & CIRCULATE CMT UP ANNULUS. POOH & TOP OFF.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/24/2013 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

12/23/13: CIBP @ 2900' WITH 5 SX CMT. PLUG AT 1750' WITH 20 SX CMT. DID NOT CIRCULATE. WELL ON VACUUM. 12/24/13: TAG TOP OF CMT PLUG @ 2700'. LOAD 4 1/2" CASING. RAN TBG TO 1700'. SPOT 25SX CMT PLUG. FULL RETURNS OUT ANNULUS. TOOH W/TBG. RAN BOND LOG. TOC @ 1030'. FLUID IN CASING FELL TO 540'. SUSPECT GLORIETTA CASING LEAK. SET CIBP @ 668' & FILL CASING WITH WATER. RE-RAN CBL. NO CMT BEHIND 4 1/2" FROM 668' TO 0'. PERFORATE @ 664'. INJECTION RATE 4 BPM @ 100#. CIRCULATE CMT TO SURFACE USING 255 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2946	2998		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

KCC-WICHITA
JAN 07 2014
RECEIVED

District: 01

RECEIVED

DEC 30 2013

KCC DODGE CITY

Signed

[Handwritten Signature]
1/14/14

(TECHNICIAN)

[Handwritten Mark]