

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10146-00-01
Spot: SESENESE Sec/Twnshp/Rge: 31-32S-42W
1326 feet from S Section Line, 179 feet from E Section Line
Lease Name: MURPHY Well #: 1-31
County: MORTON Total Vertical Depth: 3350 feet

Operator License No.: 33136
Op Name: ANADARKO E & P ONSHORE LLC
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		817		WITH 2 SX CMT
CIBP		3234		
PROD 7		3326	0	WITH 450 SX CMT
SURF	10.75	561		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/09/2013 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2013 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK IN HOLE. TOP OF FISH 820'. SET CIBP @ 817' WITH 2 SX CMT & PERFORATED 7" FROM 795' -800'. PUMPED 70 BBL FRESH WATER & WELL WENT ON VACUUM. PUMPED 35 SX CMT, DUMPED 150# HULLS, PUMPED 40 SX CMT W/100# HULLS. DISPLACED WITH 13 BBL MUD & PRESSURED UP TO 3000 PSI. TAGGED TOC INSIDE 7" @ 270'. RIG UP ON 10 3/4" X 7" ANNULUS. PUMPED 8 BBL WATER & LOADED. ESTABLISHED INJECTION RATE @ 3 BPM @ 400 PSI. PUMP 155 SX CMT. SDON. 12/10/13: TAG TOC IN 7" AT 270' WITH TBG. PUMPED 45 SX CMT. CMT CIRCULATED. RIG UP ON ANNULUS & PUMP 55 SX CMT AT 500 PSI. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2685	3212		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED

DEC 13 2013

KCC DODGE CITY

Signed

1/14/14

(TECHNICIAN)

KCC WICHITA

DEC 19 2013

RECEIVED

Form CP-2/3

AM