

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20215-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 32-19S-40W  
3945 feet from S Section Line, 1280 feet from E Section Line  
Lease Name: BUEHNE Well #: 1  
County: GREELEY Total Vertical Depth: 2965 feet

Operator License No.: 7271  
Op Name: BARTLING OIL COMPANY  
Address: 1001 CANYON EDGE DR  
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2920		
PROD	4.5	2970	0	WITH 400 SX CMT
SURF	8.625	287		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2013 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Revd. from: GUS OCHSNER Company: BARTLING OIL Phone: (512) 795-9593

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2013 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 20 SX CMT & 50# HULLS TO 2901' VIA TBG. TBG STUCK. FREEPOINT. STUCK @ 1620'. FREE @ 1610'. JET CUT TBG @ 1575'. PULL TO 1570'. (FLUID LEVEL AT 800') CIRCULATE CMT FROM 1570' TO 0' WITH 115 SX CMT & 250# HULLS. FULL RETURNS. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 15 SX CMT. PUMP 100 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS TO 75#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2895	2901		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

RECEIVED

DEC 30 2013

KCC DODGE CITY

Signed

*[Signature]*  
1/14/14

(TECHNICIAN)