

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20179-00-00
Spot: NW Sec/Twnshp/Rge: 16-19S-40W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: EVERETT Well #: 1
County: GREELEY Total Vertical Depth: 3001 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 1001 CANYON EDGE DR
AUSTIN, TX 78733

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 3000 | 0 | WITH 400 SX CMT |
| SURF | 8.625 | 259 | | WITH 200 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/19/2013 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: GUS OCHSNER Company: BARTLING OIL Phone: (512) 795-9593

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2013 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT & 250# HULLS. DISPLACE WITH WATER TO 2906'. PRESSURE TO 500#. HOLDING. TOC IN 4 1/2" @ 1600'. RAN BOND LOG. TOC @ 180'. MIRUCU. RAN TBG TO 1500'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 400#. TOP OFF 4 1/2" WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2892 | 2906 | | |

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

JAN 07 2014
RECEIVED

District: 01

RECEIVED
DEC 30 2013
KCC DODGE CITY

Signed [Signature]
1/14/14 (TECHNICIAN)