

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21760-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 26-34S-5W  
370 feet from S Section Line, 958 feet from W Section Line  
Lease Name: SEIFERT Well #: 1-26  
County: HARPER Total Vertical Depth: 5060 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5059	3100	340 SX
SURF	8.625	350		165 SX
T1	2.875	4536		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: GEORGE RAYL Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/26/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 4500' CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3100'  
PULLED CASING TO 952' SPOTTED 50 SX CEMENT. PULLED CASING TO 663'  
SPOTTED 50 SX CEMENT. PULLED CASING TO 376' CIRCULATED TO SURFACE  
WITH 150 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4880	4900		
4860	4880		
4840	4860		
4820	4900		
4710	4730		
4690	4730		
4583	4606		
4560	4606		

Remarks: COPELAND CEMENTING OUT OF BURRTON, COMMON CEMENT WITH 3% CC, TICKET #40755.

Plugged through: CSG

District: 02

Signed B. J. Hope  
1/14/14

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

DEC 26 2013

RECEIVED