

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00482-00-01
Spot: SEWNENE Sec/Twnshp/Rge: 21-20S-19W
2003 feet from S Section Line, 678 feet from E Section Line
Lease Name: THURMAN Well #: 2
County: PAWNEE Total Vertical Depth: 1008 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PLG	4.5	960		
PROD	4.5	1001	0	WITH 500 SX CMT
SURF	8.625	344		WITH 375 SX CMT

Well Type: SWD UIC Docket No: D21925.0 Date/Time to Plug: 12/20/2013 11:35 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: PUMP DOWN 4 1/2" WITH 200# HULLS & ENOUGH CMT TO FILL THE CASING TO SURFACE. PRESSURE TEST 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2013 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

POOR BOY HEAD ON THE 8 5/8" X 4 1/2" ANNULUS. RAN LINE DOWN ANNULUS & FOUND THE CMT TOP AT 6'. PUMPED 200# HULLS & 110 SX CMT DOWN THE 4 1/2" CASING. MAXIMUM PRESSURE 600 PSIG. INITIAL SHUT IN PRESSURE 100 PSIG.

Perfs:

Top	Bot	Thru	Comments
800	920		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY COPELAND ACID **KCC WICHITA**

Plugged through: CSG

JAN 07 2014

RECEIVED

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

✓ cc to UIC 1-8-14

RECEIVED

DEC 31 2013

KCC DODGE CITY

RL