

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20507-00-00
Spot: SE Sec/Twnshp/Rge: 24-21S-20W
1345 feet from S Section Line, 1336 feet from E Section Line
Lease Name: UNRUH LJ Well #: 1
County: PAWNEE Total Vertical Depth: 2330 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2000		
PROD	4.5	2322	0	WITH 125 SX CMT
SURF	8.625	900		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/30/2013 9:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SHOOT OFF TBG AT 1300' & PUMP 25 SX CMT. PERFORATE @ 900' & CIRCULATE CMT UP 8 5/8" & 4 1/2".

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2013 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

FOUND FREE POINT ON TBG AT 1300'. SHOT OFF & PULLED ONE JOINT. CEMENTED WITH 25 SX COMMON CMT & 3 % CC AT 1270'. PULLED TBG & PERFORATED AT 897'. TIED ONTO CASING & PUMPED 80 SX 60/40 POZMIX 4% GEL, DIDN'T GET ANY BLOW. TIED ONTO BACKSIDE & PUMPED 170 SX 60/40 POZMIX 4% GEL. TOPPED OFF CASING WITH 5 SX CMT. BACKSIDE & CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
1896	1948		

Remarks: USED COMMON CMT W/3% CC & 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: TBG

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

Signed Michael J. Maier
1/14/14
(TECHNICIAN)

RECEIVED

DEC 31 2013

KCC DODGE CITY