

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21165-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 27-12S-16W
2310 feet from S Section Line, 3960 feet from E Section Line
Lease Name: FROELICH B JI AND H Well #: 5
County: ELLIS Total Vertical Depth: 3574 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3573		125 SX
SURF	8.625	275		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2013 8:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: JOE SCHULTE Company: BENNETT & SCHULTE OIL CO. Phone: (785) 623-3543

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Emergency plug with rig over hole. Tubing stuck in hole. LKC- 3338' - 3376'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2013 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer Energy Services ran free point. Found tubing to be free at 2223' - 85%. Quality rigged to tubing and pumped 45 sx cement through tubing and displaced for bottom perforations. Pioneer ran in hole in tubing to 2200' and cut off tubing. Pulled tubing. Pioneer ran in hole and perforated at 1850', 1287' and 835'. Ultimate Well service ran in hole with tubing to 2000'. Quality rigged to tubing and mixed and pumped 140 sx cement w/300 # hulls to circulate cement to surface. Pulled tubing. Topped off 4 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 5 sx cement to pressure.

GPS: 38.97844 -099.09034
2059' FSL 4017' FEL
SE NE NW SW


KCC WICHITA
JAN 06 2014
RECEIVED

Remarks: QUALITY CEMENTING CO TICKET # 7629

Plugged through: TBG

District: 04

Signed


1/14/14
(TECHNICIAN)

CM

DEC 30 2013