

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20021-00-01  
Spot: NWSE Sec/Twnshp/Rge: 1-29S-34W  
1994 feet from S Section Line, 2014 feet from E Section Line  
Lease Name: LIGHT D Well #: 1  
County: HASKELL Total Vertical Depth: 5486 feet

Operator License No.: 33127  
Op Name: CHAPARRAL ENERGY, L.L.C.  
Address: 701 CEDAR LK BLVD  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2889		WITH 188 SX CMT
L1	3.5	5274		WITH 165 SX CMT
PROD	4.5	5478	0	
SURF	8.625	1820		WITH 900 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2013 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: MIGUEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Circulate hole with mud, spot 60 sx class "C" cmt w/ cotton seed hulls(5300' - 3678') to cover open perms & sqz perms behind liner. Load and test casing to 500 psi w/mud, Perf sqz holes @ 1850', break down and est circulation and to surface on 8-5/8" outlet, pump 80 sx class "C" & displace inside 3-1/2" casing to 1500'. Perf sqz holes at 800' and pump 180 sx cmt & circulate to surface. Dig out/Cut off and weld I.D plate

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2013 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 60 SX CMT WITH 200# HULLS AT 5300'. AFTER 20 HOURS, TAG TOC IN 3 1/2" LINER AT 3450'. TEST 3 1/2" LINER TO 500#. HOLDING. PERFORATE @ 1850'. INJECTION RATE 2 BPM @ 1500#. PUMP 80 SX CMT @ 2 BPM @ 500#-1500# VIA 3 1/2" LINER. HAD 75% RETURNS OUT 4 1/2" X 8 5/8" ANNULS. AFTER 4 HOURS, TEST CMT PLUG TO 1700#. HOLDING. TAG TOC IN 3 1/2" LINER @ 1120'. THIS LEAVES 25 SX CMT INSIDE 3 1/2" LINER & 55 SX CMT IN 4 1/2" X 8 5/8" ANNULUS. PERFORATE @ 800'. INJECTION RATE 2 BPM @ 3000 PSI. CIRCULATE CMT TO SURFACE WITH 200 SX, LEAVING 3 1/2" LINER & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT. PRESURE STARTED AT 3500# & ENDED AT 700#.

Perfs:

Top	Bot	Thru	Comments
5362	5366		
5292	5306		
4178	4182		
4149	4555		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

KCC WICHITA

DEC 20 2013

RECEIVED

District: 01

RECEIVED

DEC 11 2013

KCC DODGE CITY

Signed

*Ken Jehlik*  
11/18/14

(TECHNICIAN)