

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

4-29

API NUMBER: 15-077-212890000

SE-NE-NE, SECTION 18E TOWNSHIP 31 RANGE 39W

OPERATOR LICENSE # 31532

4290 FEET FROM S SECTION LINE

330 FEET FROM E SECTION LINE

OPERATOR BISON PRODUCTION CO.  
NAME & 9320 E. CENTRAL  
ADDRESS WICHITA, KS 67206

LEASE NAME: COX 1-18 148.69  
COUNTY: HARPER  
WELL TOTAL DEPTH: 4575'

PIPE: " @ "

SURFACE CASING: 8 5/8" 230'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: DUKE DRILLING COMPANY

ADDRESS: 310 W. CENTRAL, SUITE #117 WICHITA, KS 67202 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 29 MONTH: 4 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JOE LIVINGSTONES

COMPANY NAME: DUKE DRILLING COMPANY PHONE: 316-267-1331

WERE: FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH DRILL PIPE. SPOT 35 SXS. CMT. AT 1525', 35 SXS. AT 1050', 35 SXS. AT 280', 25 SXS. CMT. AT 60', 10 SXS. CMT., IN RAT HOLE, AND 10 SXS. CMT. IN MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 12:45 DAY: 29 MONTH: 4 YEAR: 1995

ACTUAL PLUGGING REPORT:

FILLED HOLE WITH HEAVY MUD. SPOTTED CEMENT THROUGH DRILL PIPE. SPOTTED 35 SXS. CMT. AT 1525', 35 SXS. CMT. AT 1050', 35 SXS. CMT. AT 280', 25 SXS. CMT. AT 60', 10 SXS. CMT. IN RAT HOLE, AND 10 SXS. CMT. IN MOUSE HOLE.

REMARKS: USED 60/40 POSMIX W/4% GEL BY ALLIED - INVOICE #1327

I DID NOT OBSERVE THIS PLUGGING.

Michael R. Wilson  
Michael R. Wilson (AGENT)

FORM CP-2/3  
REV. 3/90

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 18 1995

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 5-24-95

WELL NO. 42887