

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

7-11

API NUMBER: 15-077-213560000

100' E. of  
NE-SW-NW SECTION 16 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 5123  
OPERATOR Pickrell Drilling CO.  
NAME 110 N Market # 205  
ADDRESS Wichita KS. 67202

1650 FEET FROM SECTION LINE  
1090 FEET FROM SECTION LINE

LEASE NAME: Dirks "Q"-1  
COUNTY Harper

WELL TOTAL DEPTH: 3778' 122.79

PIPE:

SURFACE CASING 8 5/8 272'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Pickrell Drilling CO.

ADDRESS: Wichita KS LICENSE: 5123

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: \_\_\_\_\_

PLUGGING PROPOSAL RECEIVED FROM: Mike Kerns

COMPANY NAME: Pickrell Drilling PHONE: 316-262-8427

WERE: 35 Sks @ 1500 20 Sks @ WW  
35 Sks @ 1100  
35 Sks @ 320  
25 Sks @ 60  
15 Sks @ RH

RECEIVED  
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: District # 2 JUL 15 1998

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( ) NONE ( X )


COMPLETED: HOUR: 1030 DAY: 11 MONTH: 7 YEAR: 1998

CONSERVATION DIVISION  
WICHITA, KS

ACTUAL PLUGGING REPORT: The Drill pipe was run open end to 1510', where 35 Sks of cement was spotted. The Drill pipe was pulled to 1100' where 35 Sks of cement was spotted. The Drill pipe was pulled to 320' where 35 Sks of cement was spotted. The Drill pipe was pulled to 60' where cement was circulated to surface. The Rat Hole was circulated with 15 Sks of cement. The Water Well was plugged with 20 Sks of cement.

REMARKS: Allied Cementing 60/40 4% gel Ticket # 9635

I DID OBSERVE THIS PLUGGING.

  
Steve VanGieson

FORM CP-2/3  
REV. 3/90

INVOICED

DATE 7-20-98

INV. NO. 50939