



*Handwritten initials*

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. - 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 26 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

March 24, 1968.

Dear Sir:

Mr. A. D. Holiday of Mack Oil Co. has this

date requested permission to plug the following described well:

Mr. Holiday guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center Bldg. Wichita, Kansas.

Lease Name: Sayers Well No. #1

Location: C-NE-SE Sec. 30 Twp. 32S Rge. 7W (E)(W) W

County: Harper Total Depth 4850' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Holiday was instructed to plug the well as follows:

242' of 8 5/8" surface pipe circulated with 225 sacks cement.

Mud to 240 ft. 1/2 sack hulls, plug and 40 sacks cement. Mud

to 40 ft. 1/2 sack hulls Plug & 10 sacks cement to surface.

2 sacks in rathole.

Very truly yours,

*Handwritten signature*  
 Conservation Division Agent