

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 111-20

LOCATION NW NW NE

SEC. 17 TWP. 31S RGE. 9W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Anthony "D"

Operator Petroleum, Inc. Address 305 East Third, Wichita, Kansas

Field _____ County Harper

Total Depth 4780 Feet.

Plugging Contractor Garvey Drilling Company

Plugging Contractor's License No. Rotary drilled dry hole

Address Derby Bldg., Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

258 feet of 8-5/8" surface pipe circulated with cement.

Filled hole with heavy rotary mud to 254 feet.

Set plug at 254 feet. Displaced 20 sacks of cement

through the drill pipe filling hole with cement from

254 feet to 200 feet. Filled hole with mud to 15 feet.

Set second plug at 15 feet and dumped 5 sacks of cement

filling hole with cement to base of collar.

M. C. Rivers
District Conservation Agent

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1955

5-2-55
CONSERVATION DIVISION
Wichita, Kansas

DATE April 15, 1955