

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Co.

Complete Address: c/o Joe Butts, Attica, Kansas

Lease Name Detmar Well No. # 1

Location SE WCL
NE NE SE Sec. 22 Twp. 31 Rge. 9 (E) W

County Harper Total Depth 4450

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 7:00PM Day 5th Month June Year 1963

The Above well was plugged as follows:

160' of 8 5/8" surface pipe, cement circulated. 4450' of 5 1/2" long string,
cemented with 100 sacks. Sanded to 4440', cemented with 5 sacks. Hole
was filled with mud to 200', 10' rock bridge, cemented with 20 sacks.
Hole filled with mud to 40'. 10' rock bridge, cemented with 10 sacks
to base cellar.

3700' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/11/63

INV. NO. 9234-W