

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name M. E. Davis Well No. # 1

Location C NW NE NE Sec. 16 Twp. 32 Rge. 6 (E) (W)

County Harper Total Depth 4738'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 8:00AM Day 17th Month March Year 1966

The Above well was plugged as follows:

307' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged solid
with hulls on fluid at 275', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 3/21/66

INV. NO. 2894-W